

Calving front positions for 42 key glaciers of the Antarctic Peninsula Ice Sheet: a sub-seasonal record from 2013 to 2023 based on a deep learning application to Landsat multispectral imagery

Erik Loebel^{1,2}, Celia A. Baumhoer³, Andreas Dietz³, Mirko Scheinert¹, and Martin Horwath¹

¹Technische Universität Dresden, Institut für Planetare Geodäsie, Dresden, Germany

²Alfred-Wegener-Institut Helmholtz Zentrum für Polar- und Meeresforschung, Sektion Glaziologie, Bremerhaven, Germany

³German Aerospace Center, Earth Observation Center, Weßling, Germany

Correspondence: Erik Loebel (erik.loebel@tu-dresden.de)

Abstract. Calving front positions of marine-terminating glaciers are an essential parameter for understanding dynamic glacier changes and constraining ice modelling. In particular, for the Antarctic Peninsula, where the current ice mass loss is driven by dynamic glacier changes, accurate and comprehensive data products are of major importance. Current calving front data products are limited in coverage and temporal resolution because they rely on manual delineation, which is time-consuming and unfeasible for the increasing amount of satellite data. To simplify the mapping of calving fronts we apply a deep learning based processing system designed to automatically delineate glacier fronts from multispectral Landsat imagery. The U-Net based framework was initially trained on 869 Greenland glacier front positions. For this study we extended the training data by 252 front positions of the Antarctic Peninsula. The data product presented here includes 4817 calving front locations of 42 key outlet glaciers from 2013 to 2023 and achieves sub-seasonal temporal resolution. The mean difference between automated and manual extraction is estimated at 59.3 ± 5.9 m. This dataset will help to better understand marine-terminating glacier dynamics on an intra-annual scale, study ice-ocean interactions in more detail and constrain glacier models. The data is publicly available at PANGAEA under <https://doi.pangaea.de/10.1594/PANGAEA.963725> (Loebel et al., 2023).

1 Introduction

From 1992 to 2020 the Antarctic Ice Sheet lost 2671 ± 530 Gt of ice, raising the global sea level by 7.4 ± 1.5 mm (Otosaka et al., 2023). Mass loss is dominated by ice-dynamic processes, where a decrease of ice shelf thickness and extent reduces buttressing and thereby accelerates the ice flow discharge of grounded ice across the grounding line (Slater et al., 2020). At the Antarctic Peninsula (AP) in particular, increasing ice loss has been linked with ice shelf disintegration (Rott et al., 1996; Rignot et al., 2004; Rack and Rott, 2004; Cook and Vaughan, 2010). Thereby, atmospheric and oceanic influences cause ice shelf thinning and precondition collapse (Pritchard et al., 2012; Adusumilli et al., 2018). Although collapsing ice shelves do not directly contribute to sea level rise, they play an important role in stabilizing their tributary glaciers (Dupont and Alley, 2005). Once this support is lost, the dynamics of the tributary glaciers and their ice discharge increase, contributing directly to sea-level rise (Rignot et al., 2004; Seehaus et al., 2018). This mechanism has been observed in a number of cases most notably

after the collapse of the Prince Gustav ice shelf (Glasser et al., 2011) and the Larsen A and B ice shelves (Hulbe et al., 2008; Rott et al., 2011, 2018). Beyond that, even marine terminating glaciers that were not directly affected by ice shelf collapse, most of which flowing westward from the AP plateau, are experiencing changing dynamics as a result of warming climate (Cook et al., 2016; Hogg et al., 2017; Wallis et al., 2023a; Davison et al., 2024). The negative ice mass change rate of the entire AP, $-13 \pm 5 \text{ Gt yr}^{-1}$ between 1992 and 2020 and $-21 \pm 12 \text{ Gt yr}^{-1}$ between 2017 and 2020, represents 14 % (between 1992 and 2020) and 18 % (between 2017 and 2020) of the mass loss rate of the Antarctic Ice Sheet (Otosaka et al., 2023). Monitoring of AP marine terminating glaciers and ice shelves is of paramount importance for up-to-date diagnosis and reliable prediction of future changes.

One particularly important parameter of each glacier is the calving front position and its temporal variation. Firstly, calving front locations are the basis for mapping glacier area change. In this way, Cook et al. (2014) show that the majority of AP glaciers have reduced in area since the 1940s with temporal trends indicating uniform retreat since the 1970s. Most significant area losses occurred in the northeast AP and are associated with ice shelf collapse. Area loss on the west coast shows a north-south gradient and has been linked to warming ocean water (Cook et al., 2016). Secondly, calving front locations are essential for studying and understanding ice-ocean interaction as well as underlying processes. In this way, they help to understand the response of the AP to a warming climate. This applies to local studies of individual glaciers or glacier systems (Scambos et al., 2011; Seehaus et al., 2015, 2016), but also to regional studies (Friedl et al., 2018; Wallis et al., 2023a; Ochwat et al., 2024; Surawy-Stepney et al., 2024). Thirdly, calving front locations play an important role in constraining ice-dynamic models to improve simulations of future mass loss and sea level contribution (Alley et al., 2005; Barrand et al., 2013; Cornford et al., 2015). According to Pattyn and Morlighem (2020), calving is one of the key physical processes where its lack of knowledge reduces the ability to accurately predict mass changes of the Antarctic Ice Sheet and define potential tipping points. Modelling studies for Jakobshavn Isbræ in Greenland identified the calving as the dominant control with calving front migration accounting for 90 % of the acceleration (Bondizo et al., 2017). Similar conclusions are also drawn by Vieli and Nick (2011) who emphasise the need for a robust representation of the calving in ice sheet models.

Accurate calving front data with both high temporal resolution and a high spatial coverage is therefore critical. At present, however, these data products are not widely available for the AP. This is due to limitations of the manual and therefore time-consuming, process of delineating these frontal positions from the increasing amount of satellite imagery available. Table 1 gives an overview of publicly available calving front datasets for the AP. The Antarctic Digital Database (ADD) (Cook et al., 2021b) and Global Land Ice Measurements from Space (GLIMS) (GLIMS Consortium, 2005; Raup et al., 2007) products have circum-Antarctic coverage but very limited temporal resolution. The calving front data by Seehaus et al. (2015), Seehaus et al. (2016), Wallis et al. (2023b) and Surawy-Stepney (2024) are by-products of glaciological studies. Calving fronts reported by Gourmelon et al. (2022) are part of a benchmark dataset developed for evaluating automated extraction from SAR imagery. For the vast majority of the approximately 800 marine-terminating glaciers at the AP (Cook et al., 2014; Huber et al., 2017), current data products do not exploit the potential of available satellite observations. The availability of calving front positions at the AP is limited, emphasising the necessity for additional and more comprehensive data products. To generate these data products efficiently, we need to use automatic annotation methods.

Table 1. Overview of publicly available calving front datasets for the AP Ice Sheet. The number of fronts mapped by Cook et al. (2021a) is not documented. It is specified that more than 2000 aerial photographs and over 100 satellite images were used to compile the dataset.

dataset	Annotation	Sensor type	Glaciers	Mapped fronts	Time span
ADD (Cook et al., 2021a)	Manually	Optical	244		1843-2008
GLIMS (GLIMS Consortium, 2005)	Manually	Optical	>300	>900	Since 1986
Seehaus et al. (2015)	Manually	SAR	1	147	1992-2014
Seehaus et al. (2016)	Manually	SAR	1	133	1993-2014
CryoPortal (ENVEO)	Manually	SAR & Optical	16	124	2013-2017
Gourmelon et al. (2022)	Manually	SAR	5	457	1996-2020
Wallis et al. (2023b)	Manually	SAR	8	3430	2015-2021
Surawy-Stepney (2024)	Manually	SAR & Optical	9	245	2002-2023
This study (Loebel et al., 2023)	Automatic	Optical	42	4817	2013-2023

In recent years, deep learning has emerged as the tool of choice to accomplish this task (Mohajerani et al., 2019; Baumhoer et al., 2019; Zhang et al., 2021; Heidler et al., 2021; Marochov et al., 2021; Periyasamy et al., 2022; Davari et al., 2022b, a; Heidler et al., 2022; Herrmann et al., 2023). This has already been demonstrated by Baumhoer et al. (2023), who applied neural networks on SAR imagery to generate a high temporal resolution dataset of Antarctic ice shelf frontal positions. On the AP this IceLines dataset (Baumhoer et al., 2023) solely encompasses the Larsen Ice Shelf and excludes the outlet glaciers. Similar methods have been used to generate calving front data products for outlet glaciers in Greenland (Cheng et al., 2021; Zhang et al., 2023; Loebel et al., 2024c) and Svalbard (Li et al., 2023).

With this contribution, we provide a dense calving front data product for 42 key glaciers of the AP. We achieve this by applying a processing system, initially developed for Greenland, and incorporating new reference data. The locations of these glaciers are shown in Figure 1. The period covered ranges from 2013 to 2023. Glaciers were chosen based on four criteria. We process all glaciers which are (1) part of the AP Ice Sheet, (2) marine-terminating, (3) listed in the SCAR Composite Gazetteer of Antarctica (Cervellati et al., 2000) and (4) have a minimum calving front length of 5 km. The first three criteria define the scope for this dataset, our product does not include glaciers on surrounding islands nor ice shelve tributaries, the fourth criterion is related to processing limitations.

2 Methods

The processing is based on the method previously described by Loebel et al. (2024c). Originally developed for marine-terminating outlet glaciers in Greenland, the method is built with a high degree of automatization. The main modification applied to the framework is the extension of the reference dataset to incorporate glaciers on the AP. Figure 2 gives a comprehensive overview of the processing system. The steps involved are described below, followed by an accuracy assessment of the results.




Figure 1. Overview map of the Antarctic Peninsula and the 42 glaciers included in the presented data product. All glaciers lie within the drainage basins 25 and 26 mapped by Zwally et al. (2012).

2.1 Calving front delineation using deep learning

Our processing is based on multispectral Landsat-8 and Landsat-9 Level-1 data. During pre-processing, nine available satellite
80 bands, ranging from visible and infrared (VNIR) over short-wave infrared (SWIR) to thermal infrared (TIR), are cropped into 512 px × 512 px tiles with a unified ground sampling distance of 30 m, centered at the corresponding calving front. To counteract image overexposure we apply a cumulative count cut image enhancement, clipping the data between the 0.1 and 98 percentile. Furthermore, all bands are normalized between 0 and 1 by a 8-bit quantization. Ground truth reference was inferred by manual delineation for both training and testing our Artificial Neural Network (ANN). To train the model we apply 869
85 Greenland calving front positions and additional 252 calving fronts from 12 AP glaciers. Due to the similar morphology of




Figure 2. The workflow of the applied processing system divided into the various processing blocks.

Greenland and AP outlet glaciers, these 869 Greenland calving front positions represent an ideal basis for a well-generalized ANN model. The additional 12 AP glaciers are Jorum, Punchbowl, Prospect, Hektor-Green-Evans, Dryglaski, Birley, Crane, Widdowson, Drummond, Fleming, Sjogren and Boydell. Expanding the training dataset is beneficial to account for the partly different glacier morphology, such as the presence of free-floating glacier tongues. To avoid model overfitting, we make sure that the training data covers different calving and ice mélange conditions, as well as varying illumination and cloud situations.

The applied ANN performs a land cover classification where an ocean class is semantically segmented from a glacier/land class. In particular we use a modified U-Net (Ronneberger et al., 2015) with two additional contracting and expanding blocks. This modification results in a larger receptive field, which is helpful for calving front extraction (Heidler et al., 2021). 20% of the input data is used for internal model validation and model selection. Training data is augmented eight times by rotation and mirroring. For model training, we used the Adam optimization algorithm (Kingma and Ba, 2014) on a binary cross-entropy loss function for 200 epochs and randomized batches of size eight. The model output is a floating point probability mask. Each image pixel is assigned a probability between 0 (water) and 1 (glacier and land). Since the terminus length of the Hektor-Green-Evans glacier system exceeds the fixed window size, we infer five separate but partially overlapping predictions here. We then merge these five predictions by averaging the values where they overlap. During post-processing the prediction is vectorized using the Geospatial Data Abstraction Library (GDAL/OGR contributors, 2020) using a threshold of 0.5. The threshold of 0.5 is the boundary between the predicted water and glacier/land classes, i.e. the predicted coastline. The glacier front is then extracted by intersecting the predicted vectorized coastline with a static mask which is manually generated for each glacier. Masked predictions therefore only contain the calving front. This is important not only to produce a consistent data product, but also to perform a correct accuracy assessment, as the land-ocean boundary is almost static, making it easier for the ANN to delineate.

For further analysis, the calving front location shape-files are processed using the rectilinear box method (Moon and Joughin, 2008). We use this method not only to generate the time series of terminus area change but also to remove failed calving front

extractions and separate outliers. In particular, calving fronts which do not split their corresponding glaciers box are discarded as failed extractions. In addition, we separate all entries that have an area difference of more than 20 % of the corresponding box width from the previous and following entries. Separated entries are checked manually and either (1) reinserted into the dataset if they were separated due to a true area change (e. g. due to calving of a large iceberg) or (2) discarded if the area change was due to a misclassification by the ANN.

For the generation of our data product we downloaded 4991 Landsat-8 and Landsat-9 Level-1 scenes, all available data for the 42 glaciers until May 2023. These are then preprocessed into 30453 stacked (9 bands, 512 px \times 512 px) raster subsets. Since consecutive Level-1 Landsat scenes of the same path overlap, we select a maximum of one entry per day by minimising no-data pixels. The resulting 23230 raster subsets are processed by the ANN. More than half of the extractions fail, mostly due to cloud cover, leaving 8688 calving fronts. After outlier separation and checking, our final data product contains 4817 calving front positions. The success rate, which we define here as the ratio of raster subsets going into ANN processing to final quality controlled data product entries, is 21 %. All data product entries provided are full calving front extractions covering the entire calving front trajectory.

2.2 Accuracy assessment

The main accuracy assessment is done by comparing ANN-delineated calving front predictions to manual delineation for independent test imagery. The results of this comparison will validate our processing system and provide valuable metrics for comparing this method to existing studies. As an additional metric we introduce the inter-model distance. Although the inter-model distance has limited reliability, it has the advantage that it can be determined for each ANN prediction without the need for manual delineation.

2.2.1 Comparison to manual delineation

The accuracy of the data product is estimated by comparing automated calving front extractions to manual delineations. Loebel et al. (2024c) have already evaluated the processing system for accuracy and generalizability, with particular emphasis on Greenland Glaciers. Since we use additional training data for this analysis, we also apply a manually delineated test dataset specifically for the AP. This test dataset contains 60 calving front locations over 20 glaciers. This includes additional eight glaciers which are not part of the training dataset. These additional eight test glaciers ensure the spatial transferability of our method. Whereas the training data contains calving fronts from 2013 to 2021, the test dataset contains calving fronts for the separate period from 2022 and 2023. As ANN training is not deterministic, we train five separate models for our assessment. Our main error metric is the distance between the predicted delineation and the manual delineation. For this we implement two different distance estimates. Firstly, we use an average minimal distance error which we calculate by averaging the minimum distance every 30 m along the predicted front trajectory. This estimate is comparable to the ones used by Cheng et al. (2021), Loebel et al. (2022), Baumhoer et al. (2023) and Zhang et al. (2023). Secondly, we report the Hausdorff distance (Huttenlocher et al., 1993) which only considers the largest distance of all minimal distances along the two trajectories. The Hausdorff

Table 2. Results of the accuracy assessment presented as mean values with corresponding standard deviations calculated over the five trained models. The average minimal distance and the Hausdorff distance estimates are provided as mean and median values over the test dataset. Additionally shown are accuracy, precision, recall and F1-Score are given. Binary classification metrics relate to the land/glacier class.

Average minimal distance		Hausdorff distance		Binary classification metrics			
Mean (m)	Median (m)	Mean (m)	Median (m)	Accuracy	Precision	Recall	F1-Score
59.3 ± 5.9	33.9 ± 1.5	405.1 ± 20.7	257.0 ± 14.7	0.984 ± 0.001	0.978 ± 0.002	0.995 ± 0.001	0.986 ± 0.001

140 distance is therefore very sensitive to discrepancies even along small sections of the glacier front between the ANN and the manually derived calving front.

Figure 3 shows six test images for a diverse range of challenging conditions concerning ice mélange, cloud cover, iceberg presence, low illumination and satellite scene borders. In addition, the minimal distance along the predicted trajectory (from A to B) is shown for each image. Our processing system reliably delineates calving fronts from a wide range of image conditions. 145 These include a wide range of ocean, ice mélange and illumination conditions, light cloud cover, and images with calving fronts near the edge of a satellite scene. This is due to the large training dataset, which covers a wide variety of satellite images under these conditions. In addition, the integration of multispectral input data leads to more accurate predictions under these difficult situations than using only single bands inputs (Loebel et al., 2022). Looking at the distance error along the predicted fronts, it is clear that the difference between manual delineation and ANN is not uniform. This is also reflected in the Hausdorff and 150 average minimum distance errors, which can vary widely. Large minimal distance errors mostly occur due to inaccurate ANN predictions at difficult-to-delineate parts of the glacier front (e. g. at ~ 11 km in Fig. 3 (f) or at ~ 15 km in Fig. 3 (c)). However, it is important to note, that although we treat it as such here, our manual delineation is not a traditional ground truth, as it is also uncertain depending on the author and the satellite image. For difficult-to-delineate scenes (e. g. Prospect Glacier in Fig. 3 (d)), it is not possible to attribute the error as both the manual and ANN predictions are uncertain.

155 Table 2 gives an overview of the accuracy assessment over the entire test dataset. In addition to the average minimal distance and the Hausdorff distance estimates, we also specify the binary classification metrics accuracy, precision, recall and F1-Score. Whilst a high binary classification performance does not necessarily translate to an accurate prediction of the calving front trajectory, we report these values to facilitate comparability of our results with other studies and datasets. Although completely different test datasets are involved, the 59.3 ± 5.9 m mean average minimal distance calculated here aligns very well with the 160 61.2 ± 7.5 m reported by Loebel et al. (2024c). When applied to the ESA-CCI (ENVEO, 2017) and CALFIN (Cheng et al., 2021) test datasets (as processed in Loebel et al. (2024c)), which contain a further 100 and 110 additional test images from Greenland glaciers, respectively, we calculate a mean average minimal distance of 79.1 ± 5.3 m and 78.7 ± 3.8 m (see extended accuracy assessment table in supplement). Furthermore these results are in the broad range of other ANN-based calving front extraction methods using optical imagery like Cheng et al. (2021) with 86.7 ± 1.4 m and Zhang et al. (2023) with 79 m. The 165 Hausdorff distance is commonly not reported in other automated glacier front delineation studies. However, Goliber et al. (2022) estimated the error in manual delineation by applying the median Hausdorff distance to duplicate delineations from




Figure 3. Accuracy assessment results of 6 sample scenes from the test dataset. Dashed black lines show manually delineated calving fronts. Graphs at the bottom of each image show the minimal distance along the predicted trajectory (from A to B). Red lines show the five ANN predictions from five models. Overlap of lines is indicated by higher color intensity. Average minimal distance and Hausdorff distances are given for each test image. Note that the endpoints B of different models do not coincide due to the different lengths of the predicted fronts. For location of specific glaciers, see Figure 1. Landsat imagery courtesy of the U.S. Geological Survey.




Figure 4. Histogram of the average minimal distance between manual delineation and ANN prediction. The number of total test scenes corresponds to the test dataset multiplied by the 5 trained ANN models. The overall median is shown as a dotted line and the overall mean as a dashed line. Grey levels indicate whether the test scene is from a glacier that is part of the training dataset or not.

different authors. Depending of the pairs of authors median errors range from 58.6 m to 7350 m with an overall median error of 107 m. This suggests that our method, which has a median Hausdorff error of 257 ± 14.7 m, is in the range of possible manual delineation errors, but has not yet reached human performance.

170 When assessing the accuracy only for the 23 test scenes of glaciers outside the training dataset we calculate a mean delineation error of 51.9 ± 6.7 m (median: 37.3 ± 5.3 m). Interestingly, the mean is lower and the median is higher than for an assessment over the 37 scenes from glaciers within the training dataset, where we mean (and median) delineation error is 65.3 ± 7.7 m (median: 33.8 ± 1.5 m). This is likely because of training glaciers that have challenging-to-delineate calving conditions (like Prospect Glacier, see Fig. 3 (d)). Figure 4 shows the distribution of the average minimal distance error accumulated
 175 over all test scenes for the 5 trained models. Based on these numbers, we confirm the high degree of ANN model generalization and hence the spatial transferability of our method.

2.2.2 Inter-model distance

As a secondary estimate of accuracy, we introduce the inter-model distance. We define the inter-model distance as the average minimal distance between two predicted calving front trajectories from two different ANN models that have the same architecture and use the same set of hyperparameters. Specifically for our case, we calculate a mean inter-model distance between the
 180 ANN model we use to generate our data product (randomly selected) and the four other trained models. The concept behind this metric is that the variability of different models predicting the same calving front is highly correlated with the accuracy of those predictions. The main motivation for introducing the mean inter-model distance is that it can be calculated for each calving front prediction without the need for manual delineation. Hence, the mean inter-model distance can be reported for each
 185 entry in our data product. However, limitations need to be considered when evaluating this metric. Although a low inter-model




Figure 5. Histogram of the mean inter-model distance over all calving front entries in our data product. The overall median is shown as a dotted line and the overall mean as a dashed line. Grey levels indicate whether the test scene is from a glacier that is part of the training dataset or not.

distance confirms that the ANN is confident in its prediction, it does not necessarily translate into an accurate calving front. Systematically incorrect predictions from all five ANN models (e.g. due to an iceberg being misclassified as a glacier) result in a low mean inter-model distance, when in fact the predicted front would be of low quality with a large distance to manual delineation. That said, as incorrect predictions are mostly eliminated during quality control of the data product (see Sect. 2), the opposite is more likely to happen. Here, a high mean inter-model distance is calculated, although the predicted front is of good quality. This happens most often in satellite scenes with difficult image conditions where the ANN predictions have low confidence, causing some models to delineate the front correctly. An accurately delineated calving front prediction can therefore yield a high mean inter-model distance when at least one of the predictions of the other four models are of low quality. Overall, we believe that this mean inter-model distance is a useful estimate of accuracy, although it will likely overestimate the delineation error for some calving front predictions.

Figure 5 shows the distribution of the mean inter-model distance over all calving front entries in our data product. Again, we distinguish whether the entire is from a glacier that is part of the training dataset or not, further validating spatial transferability. Across our entire data product we calculate a mean of 107.9 m and a median of 33.2 m. While the mean value is significantly higher than the mean average minimal distance of our test dataset, the median values are almost the same. It should also be noted that the mean inter-model distance varies considerably from glacier to glacier. Separate histograms for each of the 42 glaciers are included in the supplement.

3 Data product and usage notes

The data product presented here has been created to provide glaciologists and glacier modellers with high quality calving front positions of the AP Ice Sheet without the need for manual delineation. Figure 1 gives a spatial overview of the 42 processed

Table 3. Temporal coverage of our ANN generated time series. The numbers and the color intensity indicate the amount of processed calving front positions in the respective year.

	Jorum	Punchbowl	Prospect	Hektoria-Green-Evans	Drygalski	Birley	Bleriot	Crane	Dins-Bomb-Edge	Hugi	Murphy Wilkinson	Stringfellow	Trooz	Wildowson	Drummond	Coyley	Fleming	Harriot	Boydell	Sjogren	Abyuk	Cadman	Funk	Carlson	Clarke	Remus-Snowshoe	Swishbank	Helm	Volat	Peter	McCance	Hopkins	Erskine	Keith	Oilet	Renard-Krebs	Temple	Mahorad	Pyke	Dorv-Dorv-Desu	Akaga-Simon	Zocher	
2013	5	5	4	2	2	7	4	5	3	7	4	4	7	7	7	4	9	8	3	3	4	8	8	10	5	7	5	6	0	2	7	7	5	8	7	5	6	5	2	3	2	2	
2014	8	8	11	10	17	13	11	10	16	14	21	10	14	11	11	11	14	11	12	12	13	6	6	17	12	16	12	20	6	8	12	13	11	12	7	10	13	10	6	14	10	10	
2015	12	12	15	8	18	9	15	15	17	12	9	11	11	9	9	14	14	10	17	17	6	8	8	16	7	16	15	12	4	6	10	10	8	9	10	12	12	6	10	18	11	11	
2016	13	13	10	14	19	11	8	15	8	14	16	8	10	11	11	7	10	8	11	11	7	6	6	9	6	12	9	17	9	6	12	10	12	11	8	8	12	7	8	14	8	8	
2017	13	13	12	8	15	10	13	13	16	10	9	10	10	7	7	11	13	14	14	14	9	8	8	17	11	16	15	13	9	7	10	8	8	10	4	13	14	10	12	19	9	9	
2018	18	18	11	7	15	8	8	15	9	14	13	4	10	11	11	8	11	14	14	14	12	7	7	11	13	17	13	12	4	7	13	8	12	14	9	6	9	5	9	11	8	8	
2019	9	9	14	6	16	10	11	8	15	12	21	8	11	11	11	14	16	11	12	12	6	6	6	23	13	15	15	12	3	12	15	9	15	16	10	12	13	8	10	11	7	7	
2020	14	14	7	9	18	13	12	15	19	12	18	6	17	9	9	7	8	8	13	13	12	6	6	8	6	12	11	8	11	4	13	10	13	13	13	11	11	8	16	16	11	11	
2021	16	16	10	13	27	11	6	17	22	11	13	12	12	8	8	9	10	11	16	16	7	3	3	9	7	16	8	8	6	7	10	9	7	8	10	6	9	7	14	18	7	7	
2022	15	15	17	12	30	10	5	23	21	15	21	11	17	13	13	7	20	18	25	25	13	4	4	23	7	24	20	19	20	9	11	10	14	20	10	10	14	9	13	21	3	3	
2023	7	7	4	4	12	6	5	11	12	7	7	2	3	6	6	4	5	5	10	10	2	1	1	9	11	10	10	7	7	4	5	5	5	5	3	4	3	1	8	15	6	6	
Total	130	130	115	93	189	108	98	147	158	128	152	86	122	103	103	96	130	118	147	147	97	63	63	152	98	161	133	134	79	72	118	99	110	126	91	97	116	76	108	160	82	82	4817

205 glaciers. A tabular overview is given in Table 3. In total the data record encompasses 4817 calving front positions over 42 marine-terminating glaciers. Since the data is derived from optical imagery, the time series have a 14-week gap during polar night from May to mid-August. Outside polar night, the dataset has one entry every 19.5 days on average. However, the sampling is irregular and primarily dependent on the satellite orbit and cloud cover. The time frame from 2013 to 2023 covers that of the IceLines dataset (Baumhoer et al., 2023), facilitating a combined analysis of circum-Antarctic calving front change.

210 Figure 6 gives eight example time series of terminus area change within two regions of the AP. The terminus area change of glaciers in the Larsen-B embayment (Fig. 6 a-d) is spatially correlated and shows a steady advance from 2013 until the end of 2021. At the beginning of 2022, our data show a simultaneous retreat of the four glaciers. Subsequently, the glacier tongues of Hektoria-Green-Evans, Jorum, and Crane glacier have collapsed. This simultaneous retreat is attributed to the disintegration of landfast sea ice inside the embayment in early 2022 and the resulting loss of buttressing (Ochwat et al., 2024). The glaciers in Wordie Bay (Fig. 6 e-h) show a more varied calving front dynamics. These range from stable calving front positions (Harriot Glacier and Carlson since mid 2020) over steady terminus advance superimposed by frequent calving events (Fleming Glacier) to large calving events (Prospect Glacier in 2018). The dynamic changes in this area are linked to the Wordie Ice Shelf and its disintegration between the 1960s and the late 1990s. This has led to an increased ice flow and calving of the three main tributary glaciers Harriot, Fleming, Carlson and Prospect (Friedl et al., 2018). Therefore, an operational and temporally high resolution monitoring of these glaciers is particularly important. An overview of the the time series of all 42 glaciers of our data product is given in the supplement.

To put our data product in context with existing datasets, we contrast the different time series. Figure 7 shows time series of glacier advance for three examples. For each glacier, all available datasets were used (see Tab. 1). For the Dinsmoor-Bombardier-Edgeworth glacier system (Fig. 7 (a)), there is generally very good agreement between the four datasets. Here, our data product provides a valuable continuation of the time series of Seehaus et al. (2015), which was delineated as part of a glaciological study (Seehaus et al., 2015) for this glacier. Similarly, for the Keith Glacier (Fig. 7 (b)), the dataset of Wallis et al.




Figure 6. Example time series of terminus area change generated by our processing system for (a-d) four AP glacier in the Larsen-B embayment and (e-g) three glaciers at Wordie Bay. Color-coded calving front locations are depicted in the maps in the left. Corresponding time series are shown on the right with entries marked by black dots. The blue dots are additional validation marks that indicate the frontal positions of the manually delimited reference dataset. Landsat imagery courtesy of the U.S. Geological Survey.




Figure 7. Time series of glacier advance along central flowline for (a) the Dinsmore-Bombardier-Edgeworth glacier system, (b) Keith Glacier and (c) Drygalski Glacier. The individual datasets are marked with different colours. Note that the axes have differing scales.

(2023a) has significant overlap with our time series. Although calving front change during this period is relatively small, the seasonal and subseasonal variations are captured by both datasets. Importantly differences between these time series are in the range of both manual and ANN delineation accuracy. The time series of Drygalski Glacier (Fig. 7 (c)) is representative for the majority of glaciers in our data product. Here our time series is the first seasonal record, with the other available datasets being the GLIMS database (GLIMS Consortium, 2005) and the ADD (Cook et al., 2021b). These three examples highlight that the quality of our automatically delineated calving fronts is comparable to existing manually extracted datasets. As a result, our data product is the first to combine seasonal temporal resolution with a large spatial coverage across the AP. Nevertheless, the importance of the GLIMS and ADD products must be emphasised, as these are still the only repositories that provide complete coverage and, the ADD in particular, long term observations ranging back to 1843.

The data product is stored in a georeferenced vector file format (GeoPackage and ESRI Shapefile), sorted by glacier and date within a file system structure. All files are georeferenced using the Antarctic Polar Stereographic Projection (EPSG:3031). This allows for easy handling, e.g. by means of GIS software or geospatial data libraries. Calving front traces are stored separately for each glacier and each date, as well as in a consolidated file. In addition to the full data product, annual entries are provided for each glacier. Annual entries also contain the full ANN coastline predictions which are provided as both linestings and polygonal masks. The attribute table of each file includes the glacier name, calving front date, type (glacier front or coastline), processing date, processing version, corresponding Landsat product identifier, mean inter-model distance and standard deviation of the inter-model distance. The file naming convention for each entry is: *[glacier name]_[YYYYMMDD]_[type].shp*. An example entry would be: *prospect_20230408_glacier_front.shp*.

245 4 Data and code availability

The AP calving front location data record is publicly available at PANGAEA under <https://doi.pangaea.de/10.1594/PANGAEA.963725> (Loebel et al., 2023). The calving front locations can be downloaded by clicking on the "View Dataset as HTML" button in the overview. All reference data applied in this study is publicly available. Greenland reference data is available at <http://dx.doi.org/10.25532/OPARA-282> (Loebel et al., 2024d) and AP reference data is available at <https://doi.org/10.25532/OPARA-581> (Loebel et al., 2024b). We provide a containerized implementation (platform: Docker) of the presented processing system. The software automatically extracts calving front positions from Landsat-8 or Landsat-9 Level-1 data archives for glaciers used within this study or at user-defined coordinates. This enables the analysis of glaciers that are outside our reference dataset or beyond the temporal frame of our study. The software is available at <https://github.com/eloebel/glacier-front-extraction> (last access 24 July 2024) and <https://doi.org/10.5281/zenodo.7755774> (Loebel, 2023a). Our implementation (software: Python 3) of the rectilinear box method is available at <https://github.com/eloebel/rectilinear-box-method> (last access 24 July 2024) and <https://doi.org/10.5281/zenodo.7738605> (Loebel, 2023b). The processed time series of terminus area change, provided in text file format, are available at <https://doi.org/10.25532/OPARA-557> (Loebel et al., 2024a).

5 Conclusions

260 Accurate as well as temporally and spatially comprehensive calving front data is essential for understanding and modelling glacial evolution. This paper addresses this requirement and presents a new data record for glaciers at the AP. The data is generated by applying multispectral Landsat-8 and Landsat-9 imagery to a deep learning based processing system. We validated the processing system for accuracy, robustness, and generalization capabilities using independent test data. The mean difference between automated and manual extraction is estimated at 59.3 ± 5.9 m. The resulting data record contains 4817 calving front locations for 42 key outlet glaciers from 2013 to 2023. It achieves sub-seasonal temporal resolution for all processed glaciers, making it a valuable addition to existing data records.

More broadly, this contribution exemplifies that well generalised ANN processing systems can be applied to various regions of interest with only minor additions to reference data. With thousands of marine-terminating glaciers worldwide (RGI Consortium, 2017), this is particularly relevant for extracting calving fronts. We expect that our presented data record will not only advance glaciological research for the AP, but also contribute to future deep learning based calving front data products and data inter-comparison projects.

Author contributions. Contributions are according to CRediT. Conceptualization: EL, CAB, AD and MS. Data curation: EL. Formal analysis: EL. Funding acquisition: MH, MS, AD. Investigation: EL. Methodology: EL. Software: EL. Supervision: CAB, AD, MH, MS. Validation: EL. Visualization: EL. Writing (original draft): EL. Writing (review and editing): EL, CAB, MH and MS.

275 *Competing interests.* The author declares that there are no competing interests.

Acknowledgements. We thank the USGS for providing Landsat-8 and Landsat-9 imagery. We are grateful to the TU Dresden Center for Information Services and High Performance Computing (ZIH) for providing their high-performance and storage infrastructure. We acknowledge the Norwegian Polar Institute's Quantarctica package. This work was supported by the Helmholtz Association of German Research Centers as part of the Helmholtz Information and Data Science Incubator, project "Artificial Intelligence for Cold Regions" (AI-CORE, grant no. ZT-I-0016), and by the German Federal Ministry of Education and Research (BMBF), project "Greenland Ice Sheet/Ocean Interaction" (GROCE2, grant no. 03F0778G).

280

References

- Adusumilli, S., Fricker, H. A., Siegfried, M. R., Padman, L., Paolo, F. S., and Ligtenberg, S. R.: Variable basal melt rates of Antarctic Peninsula ice shelves, 1994–2016, *Geophysical Research Letters*, 45, 4086–4095, <https://doi.org/10.1002/2017GL076652>, 2018.
- 285 Alley, R. B., Clark, P. U., Huybrechts, P., and Joughin, I.: Ice-sheet and sea-level changes, *science*, 310, 456–460, <https://doi.org/10.1126/science.1114613>, 2005.
- Barrand, N. E., Hindmarsh, R. C., Arthern, R. J., Williams, C. R., Mouginit, J., Scheuchl, B., Rignot, E., Ligtenberg, S. R., Van Den Broeke, M. R., Edwards, T. L., et al.: Computing the volume response of the Antarctic Peninsula ice sheet to warming scenarios to 2200, *Journal of Glaciology*, 59, 397–409, <https://doi.org/10.3189/2013JoG12J139>, 2013.
- 290 Baumhoer, C. A., Dietz, A. J., Kneisel, C., and Kuenzer, C.: Automated Extraction of Antarctic Glacier and Ice Shelf Fronts from Sentinel-1 Imagery Using Deep Learning, *Remote Sensing*, 11, 2529, <https://doi.org/10.3390/rs11212529>, 2019.
- Baumhoer, C. A., Dietz, A. J., Heidler, K., and Kuenzer, C.: IceLines—A new data set of Antarctic ice shelf front positions, *Scientific Data*, 10, 138, 2023.
- Bondizo, J. H., Morlighem, M., Seroussi, H., Kleiner, T., Rückamp, M., Mouginit, J., Moon, T., Larour, E. Y., and Humbert, A.: The mechanisms behind Jakobshavn Isbræ’s acceleration and mass loss: A 3-D thermomechanical model study, *Geophysical Research Letters*, 44, 6252–6260, <https://doi.org/10.1002/2017GL073309>, 2017.
- 295 Cervellati, R., Ramorino, C., Sievers, J., Thomson, J., and Clarke, D.: A composite gazetteer of Antarctica, *Polar Record*, 36, 278–285, <https://doi.org/10.1017/S0032247400016739>, 2000.
- Cheng, D., Hayes, W., Larour, E., Mohajerani, Y., Wood, M., Velicogna, I., and Rignot, E.: Calving Front Machine (CALFIN): Glacial Termini Dataset and Automated Deep Learning Extraction Method for Greenland, 1972–2019 , *The Cryosphere*, 15, <https://doi.org/10.5194/tc-15-1663-2021>, 2021.
- 300 Cook, A., Vaughan, D., Luckman, A., and Murray, T.: A new Antarctic Peninsula glacier basin inventory and observed area changes since the 1940s, *Antarctic Science*, 26, 614–624, <https://doi.org/10.1017/S0954102014000200>, 2014.
- Cook, A., Fox, A., and Thomson, J.: Coastal change data for the Antarctic Peninsula region, 1843 to 2008 (Version 1.0) [Data set], <https://doi.org/10.5285/07727663-9B94-4069-A486-67E4D82177D3>, 2021a.
- 305 Cook, A. J. and Vaughan, D. G.: Overview of areal changes of the ice shelves on the Antarctic Peninsula over the past 50 years, *The cryosphere*, 4, 77–98, <https://doi.org/10.5194/tc-4-77-2010>, 2010.
- Cook, A. J., Holland, P., Meredith, M., Murray, T., Luckman, A., and Vaughan, D. G.: Ocean forcing of glacier retreat in the western Antarctic Peninsula, *Science*, 353, 283–286, <https://doi.org/10.1126/science.aae0017>, 2016.
- 310 Cook, S. J., Christoffersen, P., Truffer, M., Chudley, T. R., and Abellán, A.: Calving of a Large Greenlandic Tidewater Glacier has Complex Links to Meltwater Plumes and Mélange, *Journal of Geophysical Research: Earth Surface*, 126, e2020JF006051, <https://doi.org/https://doi.org/10.1029/2020JF006051>, e2020JF006051 2020JF006051, 2021b.
- Cornford, S. L., Martin, D., Payne, A., Ng, E., Le Brocq, A., Gladstone, R. M., Edwards, T. L., Shannon, S. R., Agosta, C., van den Broeke, M. R., et al.: Century-scale simulations of the response of the West Antarctic Ice Sheet to a warming climate, *The Cryosphere*, 9, 1579–1600, <https://doi.org/10.5194/tc-9-1579-2015>, 2015.
- 315 Davari, A., Baller, C., Seehaus, T., Braun, M., Maier, A., and Christlein, V.: Pixelwise Distance Regression for Glacier Calving Front Detection and Segmentation, *IEEE Transactions on Geoscience and Remote Sensing*, 60, 1–10, <https://doi.org/10.1109/TGRS.2022.3158591>, 2022a.

- Davari, A., Islam, S., Seehaus, T., Hartmann, A., Braun, M., Maier, A., and Christlein, V.: On Mathews Correlation Coefficient and Improved Distance Map Loss for Automatic Glacier Calving Front Segmentation in SAR Imagery, *IEEE Transactions on Geoscience and Remote Sensing*, 60, 1–12, <https://doi.org/10.1109/TGRS.2021.3115883>, 2022b.
- Davison, B. J., Hogg, A. E., Moffat, C., Meredith, M. P., and Wallis, B. J.: Widespread increase in discharge from west Antarctic Peninsula glaciers since 2018, *The Cryosphere*, 18, 3237–3251, <https://doi.org/10.5194/tc-18-3237-2024>, 2024.
- Dupont, T. and Alley, R.: Assessment of the importance of ice-shelf buttressing to ice-sheet flow, *Geophysical Research Letters*, 32, 2005.
- ENVEO: Ice Flow and Calving Front – Timeseries, <https://cryoportalenveo.at/iv/calvingfront/>, accessed: 2023-09-08.
- ENVEO: Greenland Calving Front Dataset, 1990–2016, v3.0, <http://products.esa-icesheets-cci.org/products/downloadlist/CFL>, (last access: 11.November 2021), 2017.
- Friedl, P., Seehaus, T. C., Wendt, A., Braun, M. H., and Höppner, K.: Recent dynamic changes on Fleming Glacier after the disintegration of Wordie Ice Shelf, Antarctic Peninsula, *The Cryosphere*, 12, 1347–1365, <https://doi.org/10.5194/tc-12-1347-2018>, 2018.
- GDAL/OGR contributors: GDAL/OGR Geospatial Data Abstraction software Library, Open Source Geospatial Foundation, <https://gdal.org>, 2020.
- Glasser, N., Scambos, T., Bohlander, J., Truffer, M., Pettit, E., and Davies, B.: From ice-shelf tributary to tidewater glacier: continued rapid recession, acceleration and thinning of Röhss Glacier following the 1995 collapse of the Prince Gustav Ice Shelf, Antarctic Peninsula, *Journal of Glaciology*, 57, 397–406, <https://doi.org/10.3189/002214311796905578>, 2011.
- GLIMS Consortium: GLIMS Glacier Database, Version 1, <https://doi.org/10.7265/N5V98602>, 2005.
- Goliber, S., Black, T., Catania, G., Lea, J. M., Olsen, H., Cheng, D., Bevan, S., Bjørk, A., Bunce, C., Brough, S., Carr, J. R., Cowton, T., Gardner, A., Fahrner, D., Hill, E., Joughin, I., Korsgaard, N. J., Luckman, A., Moon, T., Murray, T., Sole, A., Wood, M., and Zhang, E.: TermPicks: a century of Greenland glacier terminus data for use in scientific and machine learning applications, *The Cryosphere*, 16, 3215–3233, <https://doi.org/10.5194/tc-16-3215-2022>, 2022.
- Gourmelon, N., Seehaus, T., Braun, M., Maier, A., and Christlein, V.: Calving fronts and where to find them: a benchmark dataset and methodology for automatic glacier calving front extraction from synthetic aperture radar imagery, *Earth System Science Data*, 14, 4287–4313, <https://doi.org/10.5194/essd-14-4287-2022>, 2022.
- Gourmelon, N., Seehaus, T., Braun, M. H., Maier, A., and Christlein, V.: CaFFe (CALving Fronts and where to Find thEm: a benchmark dataset and methodology for automatic glacier calving front extraction from sar imagery) [Data set], <https://doi.org/10.1594/PANGAEA.940950>, 2022.
- Heidler, K., Mou, L., Baumhoer, C., Dietz, A., and Zhu, X. X.: HED-UNet: Combined Segmentation and Edge Detection for Monitoring the Antarctic Coastline, *IEEE Transactions on Geoscience and Remote Sensing*, 2021.
- Heidler, K., Mou, L., Loebel, E., Scheinert, M., Lefèvre, S., and Zhu, X. X.: Deep Active Contour Models for Delineating Glacier Calving Fronts, in: *IGARSS 2022 - 2022 IEEE International Geoscience and Remote Sensing Symposium*, pp. 4490–4493, <https://doi.org/10.1109/IGARSS46834.2022.9884819>, 2022.
- Herrmann, O., Gourmelon, N., Seehaus, T., Maier, A., Fürst, J. J., Braun, M. H., and Christlein, V.: Out-of-the-box calving-front detection method using deep learning, *The Cryosphere*, 17, 4957–4977, <https://doi.org/10.5194/tc-17-4957-2023>, 2023.
- Hogg, A. E., Shepherd, A., Cornford, S. L., Briggs, K. H., Gourmelen, N., Graham, J. A., Joughin, I., Mougintot, J., Nagler, T., Payne, A. J., et al.: Increased ice flow in Western Palmer Land linked to ocean melting, *Geophysical Research Letters*, 44, 4159–4167, 2017.
- Huber, J., Cook, A. J., Paul, F., and Zemp, M.: A complete glacier inventory of the Antarctic Peninsula based on Landsat 7 images from 2000 to 2002 and other preexisting data sets, *Earth System Science Data*, 9, 115–131, <https://doi.org/10.5194/essd-9-115-2017>, 2017.

- Hulbe, C. L., Scambos, T. A., Youngberg, T., and Lamb, A. K.: Patterns of glacier response to disintegration of the Larsen B ice shelf, Antarctic Peninsula, *Global and Planetary Change*, 63, 1–8, <https://doi.org/https://doi.org/10.1016/j.gloplacha.2008.04.001>, 2008.
- Huttenlocher, D., Klanderman, G., and Rucklidge, W.: Comparing images using the Hausdorff distance, *IEEE Transactions on Pattern Analysis and Machine Intelligence*, 15, 850–863, <https://doi.org/10.1109/34.232073>, 1993.
- Kingma, D. P. and Ba, J.: Adam: A Method for Stochastic Optimization, arXiv preprint arXiv:1412.6980, 2014.
- Li, T., Heidler, K., Mou, L., Ignéczi, A., Zhu, X. X., and Bamber, J. L.: A High-Resolution Calving Front Data Product for Marine-Terminating Glaciers in Svalbard, *Earth System Science Data Discussions*, 2023, 1–28, <https://doi.org/10.5194/essd-2023-396>, 2023.
- Loebel, E.: eloebel/glacier-front-extraction: Initial release v1.0.0 [code], Zenodo, <https://doi.org/10.5281/zenodo.7755774>, 2023a.
- 365 Loebel, E.: eloebel/rectilinear-box-method: Initial release v1.0.0 [code], Zenodo, <https://doi.org/10.5281/zenodo.7738605>, 2023b.
- Loebel, E., Scheinert, M., Horwath, M., Heidler, K., Christmann, J., Phan, L. D., Humbert, A., and Zhu, X. X.: Extracting Glacier Calving Fronts by Deep Learning: The Benefit of Multispectral, Topographic, and Textural Input Features, *IEEE Transactions on Geoscience and Remote Sensing*, 60, 1–12, <https://doi.org/10.1109/TGRS.2022.3208454>, 2022.
- Loebel, E., Baumhoer, C. A., Dietz, A., Scheinert, M., and Horwath, M.: Glacier calving front locations for the Antarctic Peninsula derived from remote sensing and deep learning from 2013 to 2023 [Data set], <https://doi.pangaea.de/10.1594/PANGAEA.963725>, 2023.
- 370 Loebel, E., Baumhoer, C. A., Dietz, A., Scheinert, M., and Horwath, M.: Terminus area change of 42 key glaciers of the Antarctic Peninsula from 2013 to 2023 derived from remote sensing and deep learning [data set], TU Dresden OpARA, <https://doi.org/https://doi.org/10.25532/OPARA-557>, 2024a.
- Loebel, E., Baumhoer, C. A., Dietz, A., Scheinert, M., and Horwath, M.: Manually delineated glacier calving front locations of 20 marine-terminating glaciers of the Antarctic Peninsula from 2013 to 2023 [data set], TU Dresden OpARA, <https://doi.org/http://dx.doi.org/10.25532/OPARA-581>, 2024b.
- 375 Loebel, E., Scheinert, M., Horwath, M., Humbert, A., Sohn, J., Heidler, K., Liebezeit, C., and Zhu, X. X.: Calving front monitoring at a subseasonal resolution: a deep learning application for Greenland glaciers, *The Cryosphere*, 18, 3315–3332, <https://doi.org/10.5194/tc-18-3315-2024>, 2024c.
- 380 Loebel, E., Scheinert, M., Horwath, M., Humbert, A., Sohn, J., Heidler, K., Liebezeit, C., and Zhu, X. X.: Manually delineated glacier calving front locations of 27 marine-terminating glaciers from 2013 to 2021 [data set], TU Dresden OpARA, <https://doi.org/http://dx.doi.org/10.25532/OPARA-282>, 2024d.
- Marochov, M., Stokes, C. R., and Carbonneau, P. E.: Image classification of marine-terminating outlet glaciers in Greenland using deep learning methods, *The Cryosphere*, 15, 5041–5059, <https://doi.org/10.5194/tc-15-5041-2021>, 2021.
- 385 Mohajerani, Y., Wood, M., Velicogna, I., and Rignot, E.: Detection of Glacier Calving Margins with Convolutional Neural Networks: A Case Study, *Remote Sensing*, 11, 74, <https://doi.org/10.3390/rs11010074>, 2019.
- Moon, T. and Joughin, I.: Changes in ice front position on Greenland’s outlet glaciers from 1992 to 2007, *Journal of Geophysical Research: Earth Surface*, 113, <https://doi.org/10.1029/2007JF000927>, 2008.
- Ochwat, N. E., Scambos, T. A., Banwell, A. F., Anderson, R. S., Maclennan, M. L., Picard, G., Shates, J. A., Marinsek, S., Margonari, L., Truffer, M., and Pettit, E. C.: Triggers of the 2022 Larsen B multi-year landfast sea ice breakout and initial glacier response, *The Cryosphere*, 18, 1709–1731, <https://doi.org/10.5194/tc-18-1709-2024>, 2024.
- 390 Otsuka, I. N., Shepherd, A., Ivins, E. R., Schlegel, N.-J., Amory, C., van den Broeke, M. R., Horwath, M., Joughin, I., King, M. D., Krinner, G., Nowicki, S., Payne, A. J., Rignot, E., Scambos, T., Simon, K. M., Smith, B. E., Sørensen, L. S., Velicogna, I., Whitehouse, P. L., A., G., Agosta, C., Ahlstrøm, A. P., Blazquez, A., Colgan, W., Engdahl, M. E., Fettweis, X., Forsberg, R., Gallée, H., Gardner, A., Gilbert, L.,

- 395 Gourmelen, N., Groh, A., Gunter, B. C., Harig, C., Helm, V., Khan, S. A., Kittel, C., Konrad, H., Langen, P. L., Lecavalier, B. S., Liang, C.-C., Loomis, B. D., McMillan, M., Melini, D., Mernild, S. H., Mottram, R., Mouginit, J., Nilsson, J., Noël, B., Pattle, M. E., Peltier, W. R., Pie, N., Roca, M., Sasgen, I., Save, H. V., Seo, K.-W., Scheuchl, B., Schrama, E. J. O., Schröder, L., Simonsen, S. B., Slater, T., Spada, G., Sutterley, T. C., Vishwakarma, B. D., van Wessem, J. M., Wiese, D., van der Wal, W., and Wouters, B.: Mass balance of the Greenland and Antarctic ice sheets from 1992 to 2020, *Earth System Science Data*, 15, 1597–1616, <https://doi.org/10.5194/essd-15-1597-2023>, 2023.
- 400 Pattyn, F. and Morlighem, M.: The uncertain future of the Antarctic Ice Sheet, *Science*, 367, 1331–1335, <https://doi.org/10.1126/science.aaz5487>, 2020.
- Periyasamy, M., Davari, A., Seehaus, T., Braun, M., Maier, A., and Christlein, V.: How to Get the Most Out of U-Net for Glacier Calving Front Segmentation, *IEEE Journal of Selected Topics in Applied Earth Observations and Remote Sensing*, 15, 1712–1723, <https://doi.org/10.1109/JSTARS.2022.3148033>, 2022.
- 405 Pritchard, H., Ligtenberg, S. R., Fricker, H. A., Vaughan, D. G., van den Broeke, M. R., and Padman, L.: Antarctic ice-sheet loss driven by basal melting of ice shelves, *Nature*, 484, 502–505, 2012.
- Rack, W. and Rott, H.: Pattern of retreat and disintegration of the Larsen B ice shelf, Antarctic Peninsula, *Annals of glaciology*, 39, 505–510, <https://doi.org/10.3189/172756404781814005>, 2004.
- Raup, B., Racoviteanu, A., Khalsa, S. J. S., Helm, C., Armstrong, R., and Arnaud, Y.: The GLIMS geospatial glacier database: A new tool for studying glacier change, *Global and Planetary Change*, 56, 101–110, <https://doi.org/https://doi.org/10.1016/j.gloplacha.2006.07.018>, *climate Change Impacts on Mountain Glaciers and Permafrost*, 2007.
- RGI Consortium: Randolph Glacier Inventory - A Dataset of Global Glacier Outlines, Version 6, <https://doi.org/10.7265/4m1f-gd79>, 2017.
- Rignot, E., Casassa, G., Gogineni, P., Krabill, W., Rivera, A., and Thomas, R.: Accelerated ice discharge from the Antarctic Peninsula following the collapse of Larsen B ice shelf, *Geophysical research letters*, 31, <https://doi.org/10.1029/2004GL020697>, 2004.
- 415 Ronneberger, O., Fischer, P., and Brox, T.: U-Net: Convolutional Networks for Biomedical Image Segmentation, In: Navab N., Hornegger J., Wells W., Frangi A. (eds) *Medical Image Computing and Computer-Assisted Intervention – MICCAI 2015.*, 9351, 234–241, https://doi.org/10.1007/978-3-319-24574-4_28, 2015.
- Rott, H., Skvarca, P., and Nagler, T.: Rapid collapse of northern Larsen ice shelf, *Antarctica, Science*, 271, 788–792, <https://doi.org/10.1126/science.271.5250.788>, 1996.
- 420 Rott, H., Müller, F., Nagler, T., and Floricioiu, D.: The imbalance of glaciers after disintegration of Larsen-B ice shelf, *Antarctic Peninsula, The Cryosphere*, 5, 125–134, <https://doi.org/10.5194/tc-5-125-2011>, 2011.
- Rott, H., Abdel Jaber, W., Wuite, J., Scheiblauer, S., Floricioiu, D., Van Wessem, J. M., Nagler, T., Miranda, N., and Van Den Broeke, M. R.: Changing pattern of ice flow and mass balance for glaciers discharging into the Larsen A and B embayments, *Antarctic Peninsula*, 2011 to 2016, *The Cryosphere*, 12, 1273–1291, <https://doi.org/10.5194/tc-12-1273-2018>, 2018.
- 425 Scambos, T. A., Berthier, E., and Shuman, C. A.: The triggering of subglacial lake drainage during rapid glacier drawdown: Crane Glacier, Antarctic Peninsula, *Annals of Glaciology*, 52, 74–82, <https://doi.org/https://doi.org/10.3189/172756411799096204>, 2011.
- Seehaus, T., Marinsek, S., Helm, V., Skvarca, P., and Braun, M.: Changes in ice dynamics, elevation and mass discharge of Dinsmoor–Bombardier–Edgeworth glacier system, Antarctic Peninsula, *Earth and Planetary Science Letters*, 427, 125–135, <https://doi.org/https://doi.org/10.1016/j.epsl.2015.06.047>, 2015.
- 430 Seehaus, T., Marinsek, S., Helm, V., Skvarca, P., and Braun, M. H.: Surface velocity fields, digital elevation models, ice front positions and grounding line derived from remote sensing data at Dinsmoor-Bombardier-Edgeworth glacier system, Antarctic Peninsula (1992–2014) [Data set], <https://doi.org/10.1594/PANGAEA.859573>, supplement to: Seehaus, T et al. (2015): Changes in ice dynamics, elevation

- and mass discharge of Dinsmoor-Bombardier-Edgeworth glacier system, Antarctic Peninsula. *Earth and Planetary Science Letters*, 427, 125-135, <https://doi.org/10.1016/j.epsl.2015.06.047>, 2015.
- 435 Seehaus, T., Marinsek, S., Skvarca, P., van Wessem, J. M., Tijm-Reijmer, C. H., Seco, J., and Braun, M. H.: Surface velocity fields, digital elevation models and ice front positions derived from multi-mission SAR remote sensing data at Sjøgren Inlet glaciers, Antarctic Peninsula [Data set], <https://doi.org/10.1594/PANGAEA.859255>, supplement to: Seehaus, T et al. (2016): Dynamic response of Sjøgren Inlet glaciers, Antarctic Peninsula, to ice shelf breakup derived from multi-mission remote sensing time series. *Frontiers in Earth Science* Section; Section: Cryospheric Sciences, 4(66), 1-13, <https://doi.org/10.3389/feart.2016.00066>, 2016.
- 440 Seehaus, T., Cook, A. J., Silva, A. B., and Braun, M.: Changes in glacier dynamics in the northern Antarctic Peninsula since 1985, *The Cryosphere*, 12, 577–594, <https://doi.org/https://doi.org/10.5194/tc-12-577-2018>, 2018.
- Seehaus, T. C., Marinsek, S., Skvarca, P., Van Wessem, J. M., Reijmer, C. H., Seco, J. L., and Braun, M. H.: Dynamic response of sjögren inlet glaciers, antarctic peninsula, to ice shelf breakup derived from multi-mission remote sensing time series, *Frontiers in Earth Science*, 4, 66, <https://doi.org/https://doi.org/10.3389/feart.2016.00066>, 2016.
- 445 Slater, T., Hogg, A. E., and Mottram, R.: Ice-sheet losses track high-end sea-level rise projections, *Nature Climate Change*, 10, 879–881, <https://doi.org/10.1038/s41558-020-0893-y>, 2020.
- Surawy-Stepney, T.: Data used in the article "The effect of landfast sea ice buttressing on ice dynamic speedup in the Larsen-B Embayment, Antarctica", <https://doi.org/10.5281/zenodo.10580710>, 2024.
- Surawy-Stepney, T., Hogg, A. E., Cornford, S. L., Wallis, B. J., Davison, B. J., Selley, H. L., Slater, R. A. W., Lie, E. K., Jakob, L., Ridout, 450 A., Gourmelen, N., Freer, B. I. D., Wilson, S. F., and Shepherd, A.: The effect of landfast sea ice buttressing on ice dynamic speedup in the Larsen B embayment, Antarctica, *The Cryosphere*, 18, 977–993, <https://doi.org/10.5194/tc-18-977-2024>, 2024.
- Vieli, A. and Nick, F. M.: Understanding and Modelling Rapid Dynamic Changes of Tidewater Outlet Glaciers: Issues and Implications, *Surveys in Geophysics* volume, 32, 437 – 458, <https://doi.org/10.1007/s10712-011-9132-4>, 2011.
- Wallis, B. J., Hogg, A. E., van Wessem, J. M., Davison, B. J., and van den Broeke, M. R.: Widespread seasonal speed-up of west Antarctic Peninsula glaciers from 2014 to 2021, *Nature Geoscience*, 16, 231–237, <https://doi.org/https://doi.org/10.1038/s41561-023-01131-4>, 455 2023a.
- Wallis, B. J., Hogg, A. E., van Wessem, J. M., and van den Broeke, M.: Data for Widespread seasonal speed-up of west Antarctic Peninsula glaciers from 2014–2021, <https://doi.org/10.5281/zenodo.7521416>, 2023b.
- Zhang, E., Liu, L., Huang, L., and Ng, K. S.: An automated, generalized, deep-learning-based method for delineating the calving 460 fronts of Greenland glaciers from multi-sensor remote sensing imagery, *Remote Sensing of Environment*, 254, 112265, <https://doi.org/10.1016/j.rse.2020.112265>, 2021.
- Zhang, E., Catania, G., and Trugman, D. T.: AutoTerm: an automated pipeline for glacier terminus extraction using machine learning and a “big data” repository of Greenland glacier termini, *The Cryosphere*, 17, 3485–3503, <https://doi.org/10.5194/tc-17-3485-2023>, 2023.
- Zwally, H. J., Giovinetto, M. B., Beckley, M. A., and Saba, J. L.: Antarctic and Greenland drainage systems, GSFC cryospheric sciences 465 laboratory, 2012.